

Jobsite Shuffle: Building Pad Answer Key

D → B → F → H → E → C → A → G

Why?

The site is first cleared, then topsoil is removed. Unsuitable soil is excavated before additional fill is brought in. The fill is placed and spread, followed by rough grading, compaction and final grading.